

Response to Request for Information No. 2

Questions and Answers:

1. What is the Engineers Estimate for the project?

The estimated project cost is \$900k.

2. What is the Contract Duration?

The contract period will be for 12 months.

3. What is the Projected start date?

Ideally work will begin on or before July 1, 2021.

4. Does the material need to AIS compliant?

The materials do not have to be AIS compliant. However, they must be NSF 61 and NSF 372 compliant. They must also be compliant with Section 1417 of the Safe Drinking Water Act.

5. Can a Rock Excavation Bid Item be added to the List of Quantities?

Yes, a rock excavation bid item has been added to the quote sheet.

6. Has the NMDOT Utility Permit been obtained for the road bore across HWY 220?

No permits for this project have been obtained. It is the responsibility of the contractor to obtain all necessary permits.

7. Will there be any costs associated with using water from existing hydrants?

There will not be a charge to use water from the existing water system.

8. Drawings 3 & 4 divide the new installation in sections i.e., A, B, C 'A-ALT, B-ALT. Will the project be awarded in Bid Lots or the entire system?

The quotes being solicited are for the entire project.

9. Response to Request for Information No. 1 identifies the need for vibratory monitoring. Are we to use the 2019 NMDOT Highway and Bridge Construction, Section 617 as the specification for this work?

Yes, please follow the guidelines set out in Section 617.